

NOTES

1. 115 kV IVT RATIO

$\frac{115,000}{\sqrt{3}} : \frac{115}{\sqrt{3}} // \frac{115}{\sqrt{3}} / \frac{115}{\sqrt{3}} \text{ V}$
2. 115 kV CT RATIO :

1800/1500/1200/900/600/300 : 1/1/1/1 A

- FOR LINE BAY
- 1800/1500/1200/900/600/300 :

1 A

- FOR TRANSFORMER BAY (CORE 1)
- 400/300/200 :

1/1/1 A

- FOR TRANSFORMER BAY (CORE 2-4)
- 500/200/100 :

1 A

- FOR HIGH SIDE TRANSFORMER BUSHING CT
3. 22 kV VT RATIO

$\frac{22,000}{\sqrt{3}} : \frac{110}{\sqrt{3}} // \frac{110}{\sqrt{3}} \text{ V}$
4. 22 kV CT RATIO

1800/1500/900 : 1/1/1/1 A

- FOR INCOMING BREAKER
- 1800/1500/900 :

1/1 A

- FOR TIE BREAKER
- 1800/900 :

1/1 A

- FOR LOW SIDE TRANSFORMER BUSHING CT
- 1800/900 :

1/1 A

- FOR NEUTRAL TRANSFORMER BUSHING CT
- 600/300 :

1/1 A



- FOR OUTGOING 22 kV
- 600/300 :

1/1 A

- FOR CAPACITOR BANK

5. THE NEUTRAL GROUNDING RESISTORS (NGR) ARE INDICATED FOR FUTURE INSTALLATION.
6. SYNCHRONIZING SCHEMATIC
- 6.1 -YP-01 SHOWN THUS, REFER TO INCOMING IVT DESIGNATIONS.
- 6.2 OBYP-01 SHOWN THUS REFERS TO RUNNING BUS IVT
- 6.3 ØB ONLY ✓ SHOWN THUS, REFERS TO THE SECONDARY WINDING OF IVT FOR PHASE"B" AND USING FULL TAP WINDING 115V FOR SYNCHRONIZING SYSTEM WITH ONE END OF THE WINDING CONNECTED WITH COMMON GROUND BUS.
- 6.4 MANUAL SYNCHRONIZING BY SYNCHROSCOPE SHALL UTILIZE INCOMING AND RUNNING SECONDARY VOLTAGES OF METERING CORES FROM"PHASE B" FOR BOTH IVT'S.
- 6.5 AUTOMATIC SYNCHRONISM VERIFICATION BY SYNCHRO CHECK RELAY (25) SHALL UTILIZE INCOMING AND RUNNING SECONDARY VOLTAGES OF RELAYING CORES FROM"PHASE B" FOR BOTH IVT'S.
7. EACH DIGITAL POWER METER (DPM) SHALL BE COMMUNICATED WITH AUTOMATIC METER READING (AMR) APPLICATION SERVER VIA SWITCH NETWORK.
8. FOR 115KV PROTECTION SYSTEM, RELAY SHALL BE DOUBLE MAIN PROTECTION RELAY (MAIN1&2) AND DIFFERENT PRODUCT/MANUFACTURER.
9. THE DEDICATED PROTECTION RELAY FOR 22 KV SWITCHGEAR SHALL BE STANDARDIZED WHICH CAN BE EITHER USED FOR INCOMING, BUS COUPLER, OUTGOING FEEDERS OR CAPACITOR BANK FEEDERS.
10. NETWORK TOPOLOGY OF SUBSTATION CONTROL AND PROTECTION SYSTEM IS TOPOLOGY 1

- 50VA/0.2/1.5VF , 50VA/3P/1.5VF  
(SIMULTANEOUS BURDEN = 100 VA)
- 20VA/5P20 , 20VA/0.5FS5 , 20VA/5P20 , 20VA/5P20
- 20VA/5P20
- 20VA/0.5FS5 , 30VA/5P20 , 30VA/5P20
- \*\*\*PARTICULAR REQUIREMENT FOR ALL 5P20 CLASS CT's  
CURRENT RATIO ERROR AT 100% OF RATED CURRENT < 0.5%  
20VA/5P20
- 50VA/0.5/1.9VF , 50VA/3P/1.9VF
- 20VA/5P20 , 20VA/0.5FS5 , 20VA/5P20 , 20VA/5P20
- 20VA/0.5FS5 , 20VA/5P20
- 20VA/5P20 , 20VA/0.5FS5
- 20VA/5P20 , 20VA/5P20
- 20VA/0.5FS5 , 20VA/5P20
- 20VA/0.5FS5 , 20VA/5P20
- \*\*\*PARTICULAR REQUIREMENT FOR ALL 5P20 CLASS CT's  
CURRENT RATIO ERROR AT 100% OF RATED CURRENT < 0.5%  
20VA/5P20



MTS COMPACT SWITCHGEAR  
(MTS = MIXED TECHNOLOGY SWITCHGEAR)

----- FUTURE

REFERENCE DRAWING

SINGLE LINE DIAGRAM.....DWG NO. FA1-011/63054

DEVICES	EXPLANATION
21, 21N	DISTANCE TIME-STEP PHASE AND GROUND DISTANCE RELAY
67	DIRECTIONAL PHASE OVERCURRENT RELAY
67N	DIRECTIONAL GROUND OVERCURRENT RELAY
25	SYNCHROCHECK RELAY
79	AUTOMATIC RECLOSING RELAY
50 BF	BREAKER FAILURE RELAY
50 51	NON-DIRECTIONAL INSTANTANEOUS AND TIME PHASE OVERCURRENT RELAY
50N 51N	NON-DIRECTIONAL INSTANTANEOUS AND TIME GROUND OVERCURRENT RELAY
51GB	NON-DIRECTIONAL GROUND BACKUP OVERCURRENT RELAY
87T	TRANSFORMER DIFFERENTIAL RELAY
87REF	TRANSFORMER RESTRICTED EARTH FAULT RELAY THIS RELAY SHALL BE INCORPORATED IN THE TRANSFORMER DIFFERENTIAL RELAY (87T)
87B	BUS DIFFERENTIAL RELAY, HIGH IMPEDANCE TYPE
95B	BUSBAR SUPERVISION RELAY FOR BUS WIRE SUPERVISION FOR 87B
27,59	UNDER/OVER VOLTAGE RELAY
90	AUTOMATIC VOLTAGE REGULATOR
50 ARC	ARC DETECTOR RELAY FOR ARC PROTECTION SYSTEM
81	UNDER FREQUENCY RELAY
60	CAPACITOR CURRENT UNBALANCE SENSING RELAY
Q	POWER FACTOR CONTROLLER
DPM	DIGITAL POWER METER
DIM	DISTRIBUTED I/O MODULE (PROVIDED IN CSCS)
V METER	DIGITAL VOLTMETER
SS	SYNCHRONIZING SWITCH,3-POSITION,AUTO-OFF-MAN
L	SYNCHRONIZING LAMP
V	VOLTMETER
F	FREQUENCY METER
S	SYNCHROSCOPE
LL	LINE INDICATING LAMP
TS	CURRENT TEST SWITCH
TS	POTENTIAL TEST SWITCH
▲	LOCATED IN THE SWITCHYARD JUNCTION BOX
●	LOCATED IN THE CONTROL AND RELAY BOARD
▼	LOCATED IN THE 22 kV SWITCHGEAR JUNCTION BOX
◇	FOR 22 kV SWITCHGEAR CONTROL & PROTECTIVE CIRCUITS
⏏	WYE CONNECTED CT OF SECONDARY WINDING
⏏	DELTA CONNECTED CT OF SECONDARY WINDING (IF ANY)
⏏	TRANSFORMER BUSHING CT OF SECONDARY WINDING, WYE CONNECTED FOR PHASE OR NEUTRAL
BCU	BAY CONTROL UNIT

BUB-M	
กองออกแบบสถานีไฟฟ้า ฝ่ายงานสถานีไฟฟ้า	การไฟฟ้าส่วนภูมิภาค
ผู้เขียน สุวิกรม	ผู้ว่าการ (แทน)
ผู้สำรวจ -	
วิศวกร สุวิกรม	
หัวหน้าแผนก วรเวช	สถานีไฟฟ้าบึงกาฬ 2 จ.บึงกาฬ
ผู้อำนวยการกอง	มิเตอร์ และ รีเลย์ไดอะแกรม
ผู้อำนวยการฝ่าย (แทน)	
รองผู้อำนวยการวิศวกรรม	BUENG KAN 2 SUBSTATION BUENG KAN PROVINCE
-	METERING AND RELAYING DIAGRAM
	ใช้แทนแบบ - ถูกแทนโดยแบบ - เขียนเสร็จวันที่ 26 ส.ค. 2563 แก้แบบวันที่ - มิติเป็น - มาตราส่วน - แบบเลขที่ FA4-011/63089 แผ่นที่ 1 ของจำนวน 1 แผ่น